


24481491

# 801-KS Local and Remote **Monitoring and Control Station**



Installation Instructions



### **Specifications**

#### Audible **LED Indicators:**

Input Req: 10-28VDC/3-14mA Rated: 80dB @ 2ft @28VDC

Input Reg: 12-24VDC/30mA ea. Secure - Green

Unsecured - Red

**Hook-Up Leads:** Alarm - Yellow

(4) 24 AWG - 6" long

BLK (C) - Common

Keyswitch:

RED (U) - Unsecured


Contacts: 5Amp/30VDC

RED (S) - Secure RED (A) - Alarm

Wire Leads: 22AWG - 6" long

# **A** IMPORTANT NOTES **A**

Unit must be equipped with MBS option for LEDs to work.



### Description

Provides local signal to assure users that a delayed egress system is functioning (code requirement). Includes audible and visual indication of lock status and delay activation. Provides two (2) SPDT switches: one momentary, one maintained, which can be wired to release lock and/or reset alarm condition. The keyswitch requires a standar 1-1/4" mortise cylinder with a standard straight cam. Unit mounts in a standard, double-gang electrical box.

### **Description of Operation**

The 801-KS is wired to a magnetic lock delayed egress system. The following is an operation sequence from normal (secure) condition, through an unauthorized egress attempt, to system reset:

#### Condition:


# 801-KS Status


Door closed and secure Unauthorized egress attempt After 15 (or 30) second delay

System reset Legal release Alarm Silent - Green LED on

Alarm Sounds - Green & Yellow LED on Alarm Sounding - Yellow & Red LED on

Alarm Silent - Green LED on Alarm Silent - Red LED on





RISER FOR GRAPHIC REFERENCE. LOCATE ALL DEVICES PER A-E/G.C./O.R. ADDITIONAL WIRING FOR OTHER DEVICES MAY BE REQUIRED.

